

**REQUEST FOR TENDER AT SUB-SUPPLIER**

General	Date:	22-10-2025
	Quotation No.:	30480
	Quotation Name:	Akkasæter Lager - og vedlikeholdshall
	Project Manager:	PEH
	Filled by:	PEH
	Project Description:	Columns, bracings, beams, HSQ, Built up frames
	Estimated Weight of Scope (tons):	Ca. 150 t
	Steel grade	S275 and S355 (all can be made out of S355)
	EPD	☒ yes ☐ no
	Execution Class (EXC)	☐ EXC1 ☒ EXC2 ☐ EXC3 ☐ EXC4
	Geometrical tolerance (EN 1090-2)	☒ class 1 ☐ class 2
	Corrosion Protection	Type of Protection
If Paint		RAL code: 7016 (not yet approved) Class: ☐ C1 ☒ C2 ☐ C3 ☐ C4 ☐ C5 Durability: ☐ L ☒ M ☐ H ☐ I Comments:
If HDG		☒ ISO1461 Min. - mμ
Intumescent Coating	Intumescent Coating	☐ Yes ☒ No
	If Intumescent Coating	Estimated weight of scope (tons): ☐ R30 ☐ R60 ☐ R120 Critical temperature: ☐ See list ☐ Use for all (°C): ☐ water-based ☐ solvent borne 1 comp. ☐ solvent b. 2 comp. List stating beam/column available: ☐ Yes ☐ No Comments:
Delivery	Terms	☒ DAP ☐ FCA
	Place	Adr: Hardangervidda 979, N-5785 Vøringsfoss, Eidfjord Kommune Country: Norway
	Time	Week: 2+3 Year: 2026
Project Material	Quantity list available	☒ Yes ☐ No
	Drawings available	☐ Yes ☒ No
	3D IFC model available	☒ Yes ☐ No
	Comments	Bolts and Hilti anchors must be included. Rebars ø20 welded to deck beams must be included There must be a minimum of 80% recycled steel in rolled profiles, and 20% in hollow profiles.
	Deadline for receiving quotation	24.10.25
	Paint for repair and touch up	Yes

DS Nor AS will provide workshop drawings.